

### **SWPPP Notes**

1. A copy of the approved Grading and Drainage plan for this project, together with a copy of the Notice of Intent (NOI) and the Storm Water Pollution Prevention Plan (SWPPP) shall be maintained on the site and available for review. Those elements of the grading and drainage plan pertinent to or referenced on the SWPPP shall be considered part of the SWPPP.
2. The Contractor shall notify the Town of Queen Creek Public Works Department at least 24 hours in advance of any inspections.
3. The operator shall obtain a dust control permit from the County and perform measures as required by the permit to prevent excess dust.
4. The operator shall perform, at a minimum, a visual inspection of the construction site once every month and within 24 hours of rainfall greater than or equal to one half inch or more. The operator shall prepare a report documenting his/her findings on the conditions of the SWPPP controls and note any erosion problem areas. The operators report is to be submitted to the Public Works Department for review and approval. Facilities shall be maintained as necessary to ensure there continued functioning. In addition, all temporary siltation controls shall be maintained in a satisfactory condition until such time that clearing and/or construction is completed, and the potential for erosion has passed.
5. The operator shall amend this plan as necessary during the course of construction to resolve any problem areas that become evident during the construction and/or during rainfalls.
6. The permittee shall file a Notice of Termination (NOT) after completion of construction and placement of final landscape materials. The NOT is to be submitted to the Public Works Department to final the SWPPP permit.
7. The permittee shall save all records, including the NOI, SWPPP, NOT, and the inspection reports, on file for a minimum of three years from the date of filing the NOT.
8. The implementation of these plans and the construction, maintenance, replacement, and upgrading of these facilities is the responsibility of the permittee/contractor until all construction is approved and the NOT is submitted to the Public Works Department.
9. The facilities shown on this plan must be constructed in conjunction with all clearing and grading activities in such a manner as to insure that sediment-laden water does not enter the drainage system or violate applicable water standards, and must be installed and in operation prior to any grading or land clearing. Wherever possible, maintain natural vegetation for silt control.

10. The Contractor's NOI must be received prior to the SWPPP permit being issued.  
The Contractor that will be pulling the G&D permit must have the SWPPP permit in their name.